

# PTW-1900 Installation Guide

Site survey, civil work, utility connections, commissioning

Document version 1.0

Manufacturer: Shenzhen Vtai Electrical Appliance Co., Ltd.

Email: [info@v-tai.com](mailto:info@v-tai.com) · WhatsApp: +86 135 0962 3269

Website: [rollinrackwasher.com](http://rollinrackwasher.com)

**Document version:** 1.0

**Product:** V-TAI PTW-1900 Roll-in Rack Trolley Washer

**Manufacturer:** Shenzhen Vtai Electrical Appliance Co., Ltd.

**Contact:** info@v-tai.com · +86 135 0962 3269

## 1. Pre-installation site survey

Before machine arrival, confirm the following at the install location. The V-TAI engineering team can perform a remote site survey from CAD drawings — submit to info@v-tai.com.

### 1.1 Floor space

Parameter	Specification
Machine footprint	1845 x 2050 mm
Door swing	1200 mm both sides (one side acts as loading, opposite as unloading)
Service clearance	1 m left + 1 m right + 600 mm rear
<b>Total recommended footprint</b>	<b>3500 x 4000 mm</b> (pit install), <b>3500 x 5500 mm</b> (ramp install)
Floor levelness	±2 mm over machine footprint
Floor load rating	Minimum 250 kg/m <sup>2</sup> (standard machine); 400 kg/m <sup>2</sup> if reinforced trolley option ordered

### 1.2 Ceiling and overhead

- Minimum ceiling height: **2900 mm** (machine 2650 mm + exhaust duct headroom)
- Vertical clearance above exhaust port: 250 mm minimum
- No sprinkler or low-hanging duct over machine envelope

### 1.3 Utility availability

Service	Specification	Notes
Electrical (electric heat)	380V / 3-phase / 50Hz / 100A breaker	60Hz / 208V / 480V variants available
Electrical (steam heat)	380V / 3-phase / 50Hz / 16A breaker	Steam version only
Water supply	3/4" cold, 2–4 bar dynamic	Soften if hardness > 12°dH
Steam supply	1" line, 8–10 bar saturated	Steam version only; ~35 kg/cycle
Drain	2" hot-water-rated, slope 1:50 to building stack	Grease trap upstream (code requirement)
Exhaust	Ø480 mm to exterior or steam-condensation hood	~60–80 m <sup>3</sup> /hour

## 1.4 Network (optional)

Ethernet RJ45 drop within 5 m of machine if integrating PLC with plant SCADA / MES (Modbus RTU, OPC-UA).

---

## 2. Civil work specifications

Two installation configurations. Choose ONE before machine arrival; civil work cannot be redone mid-project.

### 2.1 Pit installation (premium, 70% of professional installs)

The machine drops into a recessed floor pit so the chamber floor sits flush with the existing kitchen floor. Trolleys roll level in and out — no ramp resistance, no ergonomic load on operators.

#### Pit dimensions for PTW-1900:

- Pit footprint: 2000 × 2200 mm
- Pit depth: 250 mm
- Floor slope: 1:50 toward the chamber drain
- Finish: sealed concrete OR stainless steel pan liner
- Anchor points: 4 × M12 anchor bolts per machine corner (mark from CAD drawing supplied by V-TAI)

#### Civil scope of work:

1. Floor saw-cut along pit perimeter
2. Concrete excavation to 250 mm depth
3. Sub-base preparation (compacted aggregate 100 mm)
4. Drain re-routing if existing drain conflicts
5. Reinforced concrete pour, finished smooth and sloped
6. Sealing (food-grade epoxy or stainless liner)
7. Anchor bolt placement per V-TAI CAD

**Cost estimate:** USD \$3,000–\$8,000 depending on building type, local labor, and drain re-routing complexity.

### 2.2 Ramp installation (operationally flexible, 30% of installs)

The machine sits on the existing floor. A single-sided stainless ramp on the loading side bridges floor to chamber threshold. No civil work needed — relocatable if you move buildings.

#### Ramp specifications:

- Length: **1.5 m on the loading side only** (single-sided)
- Slope: 1:10 (10%)
- Material: SUS304 anti-slip diamond plate
- Height: 250 mm at chamber edge, 0 at floor edge
- Removable for chamber service access
- Standard accessory — shipped with the machine

**Footprint impact:**

- Pit install: 3500 × 4000 mm total area
- Ramp install: 3500 × 5500 mm total area (+1.5 m on the loading side)

**Operational note:** heavy loaded trolleys (200+ kg) may need a winch on the ramp. Ramp transition adds ~5–8 seconds to per-cycle load time vs pit installation.

---

## 3. Delivery & unpacking

### 3.1 What ships

The machine arrives in a wooden crate, FOB Shenzhen port:

- **Crate dimensions:** ~2100 × 2300 × 2800 mm
- **Crate weight:** ~840 kg (machine 720 kg + crate 120 kg)
- Crate is marked: "**PTW-1900 — Fragile — Keep Upright**"
- Forklift pockets on both long sides

### 3.2 Receiving inspection

Upon delivery:

1. Photograph the crate before opening — any visible damage must be claimed against the freight carrier within 7 days.
2. Open the crate top first; inspect the machine for transit damage.
3. Verify the contents against the included packing list:
  - 1 × PTW-1900 main unit
  - 1 × ramp (if ramp install)
  - 1 × PLC operator manual (printed)
  - 1 × spare nozzle kit (4 nozzles + cleaning tool)
  - 1 × spare door gasket
  - 1 × installation hardware bag (M12 anchor bolts × 4)
  - 1 × commissioning checklist (this document, or quick-reference card)

### 3.3 Moving into position

- Move with forklift only (do not pry under the machine base)
  - Use the supplied lifting eyes (4 × M16 on the machine top corners) for crane lifting
  - Place gently — chamber rotation bearing is impact-sensitive
  - Align to anchor bolts (pit install) OR center on ramp (ramp install)
-

## 4. Utility connections

Perform connections in this order: electrical → water → drain → steam (if applicable) → exhaust.

### 4.1 Electrical hookup

■ ■ **Lockout-tagout the supply breaker before connecting.** Only qualified electricians may perform electrical work.

1. Run 3-phase 380V cable from building distribution to machine rear connection box
2. Cable size: 6 mm<sup>2</sup> minimum for electric-heating PTW-1900 (70 kW)
3. Terminate L1, L2, L3, N, PE per the wiring diagram inside the connection box
4. Verify earth bond continuity (<1 Ω chassis to earth)
5. Apply power and confirm PLC powers up

### 4.2 Water supply

1. Connect 3/4" cold-water line to the inlet stub on machine rear
2. Install upstream isolation valve and water hammer arrestor
3. If hard water (>12°dH), water softener or RO pre-treatment upstream of machine
4. Pressurize and inspect all joints for leaks

### 4.3 Drain

1. Connect 2" drain line from machine bottom to building grease trap
2. Slope 1:50 minimum toward grease trap
3. Hot-water-rated PVC (Class 6) or stainless tubing
4. Install vacuum breaker if drain line rises above chamber bottom

### 4.4 Steam (steam version only)

1. Connect 1" steam line to inlet on machine left side
2. Install upstream pressure regulator (set to 8 bar)
3. Install steam trap on condensate return line
4. Pressurize and inspect for leaks

### 4.5 Exhaust

1. Connect Ø480 mm flexible duct from chamber top to exterior wall OR steam-condensation hood
2. Install backdraft damper at exterior wall termination
3. Slope duct downward away from machine to prevent condensation return

## 5. Commissioning

### 5.1 Pre-cycle checks

- All utilities connected and pressurized
- Chamber empty (no shipping protection foam left inside)
- Spray nozzles all installed and oriented correctly
- Door gasket seated evenly
- Chemical reservoirs filled (alkaline detergent + acid rinse)
- Drain valve confirmed open

### 5.2 First cycle (no-load validation)

1. Press **Power** on PLC; wait for boot screen
  2. Select **Standard 6-min** cycle profile
  3. Close doors, latch firmly
  4. Press **Start**
  5. Observe cycle phases:
    - Pre-rinse (~45 sec): low-pressure water visible through chamber window
    - Wash (~3 min 15 sec): high-pressure recirculation, detergent dosing audible
    - Drain (~20 sec)
    - Sanitization rinse (~1 min 30 sec): 82°C indicator illuminates
    - Drain + dwell (~30 sec)
1. Cycle complete; doors auto-unlatch
  2. Verify PLC cycle log shows: profile = Standard, wash temp peak, rinse temp peak  $\geq 82^{\circ}\text{C}$ , cycle duration ~6:00

### 5.3 Loaded validation cycle

1. Load a representative bakery rack trolley with 30 dirty sheet pans (or equivalent)
2. Repeat Standard 6-min cycle
3. After cycle: inspect 5 random trays for cleanliness — should be visually clean and dry-to-touch within 60 seconds
4. Document the cycle log CSV export to USB for plant records

### 5.4 Acceptance sign-off

The V-TAI commissioning engineer (or authorized service partner) will run a 5-cycle acceptance test and sign the **Acceptance Certificate** confirming:

- Machine achieves 82°C rinse on 5/5 cycles
- No leaks at any joint

- All PLC profiles execute correctly
- Operator trained (minimum 1 day-shift + 1 night-shift operator)

Acceptance Certificate is the warranty start-date document.

---

## 6. Operator training

Standard commissioning includes 1-day on-site operator training covering:

- PLC touch-screen interface walkthrough
- Cycle profile selection
- Daily startup and shutdown procedures
- End-of-shift drain and chamber wipe-down
- Detergent reservoir refill
- Basic troubleshooting (paper-jam-equivalent issues)

For extended training (multilingual, multi-shift, train-the-trainer), arrange in advance with the V-TAI sales team.

---

## 7. Post-installation contacts

- **Service hotline (China time):** +86 135 0962 3269 (WhatsApp)
  - **Service email:** info@v-tai.com
  - **Spare parts:** 4-week lead time worldwide; 1-week for North American / EU stocked SKUs
  - **Warranty registration:** complete the form sent with your Acceptance Certificate; submit to info@v-tai.com within 14 days of acceptance
- 

*This installation guide is provided as part of the V-TAI PTW-1900 standard delivery. For project-specific installation drawings, refer to your individual project's CAD packet.*